

Addendum #1
RFP08252015
Shah Center Monument Sign
McHenry County College

This Addendum is in response to the inquiries from potential bidders. This Addendum constitutes changes to the specifications as sent out in the original RFP and other pertinent information shared with all vendors. All changes and information listed on this Addendum should be considered as the official modifications to the specifications and should be included in your proposal with these in mind.

Please acknowledge your receipt of this addendum by attaching a signed copy of the addendum with your proposal response.

Received and acknowledged by: _____

-
1. Is there already 30amp service located at the site where this sign is to be located?

No, there is currently a single 20 amp line that was used for the old monument sign.

2. If not - how many lineal feet is it between the existing power supply and where the sign is to be located?

It is approximately 150 lineal feet to the existing power supply from where the proposed monument sign will be located. Electric service will be run to the east side of the building and to the electrical room located in the basement at the north east corner of the building.

3. Is there anything located in the ground between the building and sign location that we should be aware of that may impede creating a trench to bury the power cable?

The area between the building tie-in point and the proposed monument sign is lawn and one landscape bed along the east side of the building. There is one 4" PVC drain pipe near the proposed monument sign. HR Green is unaware of any other underground conflicts that may impede creating a trench to bury the power cable. It is still the responsibility of the contractor to contact J.U.L.I.E. to stake any underground utilities in the area.