

Addendum #1
IFB08112014
Surveillance System Installation & Service
McHenry County College

This Addendum is in response to the inquiries from potential bidders. This Addendum constitutes changes to the specifications as sent out in the original IFB and other pertinent information shared with all vendors. All changes and information listed on this Addendum should be considered as the official modifications to the specifications and should be included in your proposal with these in mind.

Please acknowledge your receipt of this addendum by attaching a signed copy of the addendum with your proposal response.

Received and acknowledged by: _____

1. Change to Section 5.0 Bid Specifications

Parking Lot C

- Provide and install (4) 6 strand 10gig OM3 indoor outdoor fiber to light poles to main pull box.
- Provide and install (4) Axis outdoor P1354 IP cameras. (1) On each pole.
- Provide and install (4) Axis outdoor surveillance cabinet for outdoor cameras.
- Provide and install (4) Fiber to copper media converters for outdoor cameras.
- **Vendor** shall provide boom lift for duration of project.
- Power is required at each light pole to power heater/blowers and media converters for all cameras on light pole. A licensed electrician will be required to install power.

2. The IFB specifies the VMS as Nuuo and the cameras as Axis, will McHenry County College (MCC) accept alternative products that meet or exceed the specifications of these products? **No**